

STRUCTURE BACKFILL, TYPE 2 -

<u>NOTE:</u> NO EARTHWORK DISTURBING ACTIVITY MAY COMMENCE UNTIL A STORM WATER

GENERAL NOTES Headwalls and wingwalls may be precast or cast in place.

DESIGN DATA

Live Load

The Structure shall be designed for HL-93 loading in accordance with AASHTO LRFD Bridge Design Specifications, 6th Edition, and all subsequent interim specifications.

Dead Load

Designed for self-weight plus 35 psf for future wearing surface.

HYDRAULIC DATA

DRAINAGE AREA

CULVERT CROSS SECTION No Scale

Proposed

Structure Backfill

Ground Line

★ Dimensions to be determined


3' Min.

WINGWALL SECTION

No Scale

by Unit Manufacturer

67.7 acres 198.25 cfs ROADWAY OVERFLOW WATERWAY AREA



KEYMAP NO SCALE

NOTES

SEE CONTRACT DOCUMENTS FOR THE GEOTECHNICAL REPORT. THE PRECAST STRUCTURE SUPPLIER SHALL BE RESPONSIBLE FOR THE WINGWALL AND FOUNDATION DESIGN. THE SUPPLIER SHALL SUBMIT, THROUGH THE CONTRACTOR, CALCULATIONS AND SEALED DESIGN DRAWINGS TO THE ENGINEER OF RECORD FOR APPROVAL. IF, DURING EXCAVATION FOR THE BOX CULVERT STRUCTURE AND WINGWALL FOOTINGS, THE SOILS BELOW ARE FOUND TO BE INSUFFICIENT, THE SOILS SHALL BE UNDERCUT BY AT LEAST 18 INCHES. THE SOIL EXPOSED AT THE BASE OF THE UNDERCUT SHALL BE COMPACTED AND THEN COVERED WITH A GEOTEXTILE FABRIC FOR USE UNDER RIPRAP, TYPE 1A, AND SHALL INCLUDE SUFFICIENT EXCESS TO WRAP THE AGGREGATE AS FOLLOWS: 12 INCHES OF NO. 5 STONE SHALL BE PLACED ON THE GEOTEXTILE, AND THE EXCESS GEOTEXTILE SHALL BE WRAPPED AROUND AND OVER THE NO. 5 STONE; 6 INCHES OF NO. 53 STONE SHALL BE PLACED ON THE GEOTEXTILE OVER THE NO. 5 STONE TO THE ELEVATION OF THE BOTTOM OF THE STRUCTURE AND WINGWALL

CLEAN EARTHEN FILL DIRT AND ANY OTHER FILL MATERIAL MUST BE FREE FROM ANY HAZARDOUS WASTE OR REGULATED SOLID

PROPOSED LEGEND — □ — □ — □ FENCE LINE □ — PSL — PSL — PSL — PSL — WITH CLEANOUT —— PG —— PG —— GAS LINE

STORM INLETS STORM CURB INLETS AQUA-SWIRL UNITS 45° BEND WATER VALVE FIRE HYDRANT STORTZ FDC


WV WATER VAULT GRANULAR BACKFILL ALONG STORM SEWER LINE



SZ ARCHITECT S, LLC GDB ELEVATUS ARCHITECTURE
PURSUANT TO SECTION 102 OF THE COPYRIGHTE ACT, 71 U.S.C., ALL CONCEPTS, IDEA
DESIONS, ARRANGEMENTS, DRAWINGS, AND PLANS INDICATED OR REPRESENTED B'
THIS DOCUMENT ARE COPYRIGHTED BY SZ ARCHITECTHECTS, LLC dDB ELEVATUS
ARCHITECTURE. AS SUCH ALL CONCEPTS, IDEAS, DESIGNS, ARRANGEMENTS,
DRAWINGS, AND PLANS INDICATED OR REPRESENTED BY THIS DOCUMENT ARE OWN
BY AND THE PROPERTY OF SZ ARCHITECTUS. LC dDB ELEVATUS ARCHITECTURE AND
WERE CREATED, EVOLVED AND DEVELOPED FOR IT'S OWN USE. NONE OF THE IDEAS
DESIGNS, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY
PERSON, ARCHITECTURAL OR ENGINEERING FRM, CONSTRUCTION FIRM,
SUBCONTRACTING FRM, SUPPLIER, OR CORPORATION FOR ANY PURPOSE WHATSO
WITHOUT THE WRITTEN PERMISSION OF SZ ARCHITECTS, LLC DB ELEVATUS
ARCHITECTURE.

MARNIN: RESPRODUCTION HEREOF IS A CRIMINAL OFFENSE UNDER SECTION 102 OF T COPYRIGHT ACT, 17 U.S.C.: 18 U.S.C. SEC, 506. UNAUTHORIZED DISCLOSURE MAY CONSTITUTE TRADE SECRET MISAPPROPRIATION IN VIOLATION OF IC.242-31-1 ET. SEC AND OTHER LAWS. THE CONCEPTS, IDES, DESIGNS, ARRANGEMENTS, DRAWNINS, AN PLANS DISCLOSED ARE COPYRIGHTED AND HEREIN MAY BE PATENTED OR BE THE SUBJECT OF PENDING PATENT APPLICATION. ANYONE VIOLATING THE INTENT OF THIS COPYRIGHTED TO THE PROPER STATE AND LOCAL LAWS. STATE AND LOCAL LAWS.

WRITTEN DIMENSIONS ON THESE DOCUMENTS SHALL HAVE PRECEDENCE OVER SCALE
DIMENSIONS, CONTRACTORS SHALL VERIEV AND BE RESPONSIBLE FOR ALL DIMENSION
AND CONDITIONS ON THE JOS AND THIS OFFICE WIST BE NOTIFIED OF ANY VARIATION
FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS, SHOP
DRAWINGS AND OR DETALS MUST BE SUBMITTED TO THIS OFFICE FOR REVIEW BEFOR
PROCEEDING WITH FABRICATION.






County Court Ser

Johnson (

REVISIONS DESCRIPTION

ISSUE DATE 2301301 8-30-2024 SUBMITTAL 100% Construction Document Set

CULVERT DETAILS




ELEVATUS ARCHITECTURE

111 E. Wayne Street, Suite 555, Fort Wayne, IN 46802 260 424-9080 ElevatusArchitecture.com

CONFIDENTIAL COPYRIGHT 2024 S2 ARCHITECTS, LLC dba ELEVATUS ARCHITECTURE SZ ARCHITECTS, LLC GOB ELEVATUS ARCHITECTORE
PURSUANT TO SECTION 102 OF THE COPYRIGHT ACT, 17 U.S.C., ALL CONCEPTS, ID
DESIGNS, ARRANGEMENTS, DRAWINGS, AND PLANS INDICATED OR REPRESENTED
THIS DOCUMENT ARE COPYRIGHTED BY SZ ARCHITECTS, LLC GAB ELEVATUS
ARCHITECTURE. AS SUCH ALL CONCEPTS, DEAS, DESIGNS, ARRANGEMENTS,
DRAWINGS, AND PLANS INDICATED OR REPRESENTED BY THIS DOCUMENT ARE OB
BY AND THE PROPERTY OF SZ ARCHITECTS, LLC GAB ELEVATUS ARCHITECTURE AN
WERE CREATED, EVOLVED AND DEVELOPED FOR ITS OWN USE, NONE OF THE IDE
DESIGNS, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR IDSCLOSED TO ANY
PERSON, ARCHITECTURAL OR ENGINEERING FIRM, CONSTRUCTION FIRM,
SUBCONTRACTING FIRM, SUPPLIER, OR CORPORATION FOR ANY PURPOSE WHATS
WITHOUT THE WRITTEN PERMISSION OF SZ ARCHITECTS, LLC GAB ELEVATUS
ARCHITECTURE.

STATE AND LOCAL LAWS.

WRITTEN DIMENSIONS ON THESE DOCUMENTS SHALL HAVE PRECEDENCE OVER SCALDIMENSIONS. CONTRACTORS SHALL VERIEV AND BE RESPONSIBLE FOR ALL DIMENSIS AND CONDITIONS ON THE JOS AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATION FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DRAWINGS AND OR DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR REVIEW BEFO PROCEEDING WITH FABRICATION.





County Court Sel


REVISIONS

DESCRIPTION

ISSUE DATE 2301301 8-30-2024 SUBMITTAL

100% Construction Document Set

OVERALL EROSION CONTROL PLAN



ELEVATUS ARCHITECTURE

111 E. Wayne Street, Suite 555, Fort Wayne, IN 46802 260 424-9080 ElevatusArchitecture.com S2 ARCHITECTS, LLC dba ELEVATUS ARCHITECTURE

SZ ARCHITECTS, LLC dDB ELEVATUS ARCHITECTURE
PURSUANT TO SECTION 102 OF THE COPYRIGHT ACT, 12 U.S.C, ALL CONCEPTS, IDEA
DESIGNS, ARRANGEMENTS, DRAWINGS, AND PLANS INDICATED OR REPRESENTED B'
THIS DOCUMENT ARE COPYRIGHTED BY SZ ARCHITECTS, LLC dDB ELEVATUS
ARCHITECTURE, AS SUCH ALL CONCEPTS, IDEAS, DESIGNOS, ARRANGEMENTS,
DRAWINGS, AND PLANS INDICATED OR REPRESENTED BY THIS DOCUMENT ARE OWN
BY AND THE PROPERTY OF SZ ARCHITECTS, LLC dDB ELEVATUS ARCHITECTURE AND
WERE CREATED, EVOLVED AND DEVELOPED FOR ITS OWN USE, NONE OF THE IDEAS
DESIGNS, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY
PERSON, ARCHITECTURAL OR ENGINEERING FIRM, CONSTRUCTION FIRM,
SUBCONTRACTING FIRM, SUPPLIER, OR CORPORATION FOR ANY PURPOSE WHATSO!
WITHOUT THE WRITTEN PERMISSION OF SZ ARCHITECTS, LLC dDB ELEVATUS
ARCHITECTURE.

STATE AND LOUAL LAWS.

WRITTEN DIMENSIONS ON THESE DOCUMENTS SHALL HAVE PRECEDENCE OVER SCAL


DIMENSIONS, CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIS

AND CONDITIONS ON THE JOB AND THIS OFFICE WILST BE NOTIFIED OF ANY VARIATION

FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS, SHOP

DRAWINGS AND OR DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR REVIEW BEFO

PROCEEDING WITH FABRICATION.






County Court Sand Road FRANKLIN, IND


Johnson (

REVISIONS DESCRIPTION


ISSUE DATE 2301301 8-30-2024 SUBMITTAL 100% Construction Document Set

EROSION CONTROL





ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED BY STATE OR COUNTY OFFICIALS




EROSION CONTROL NOTES

- . ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED BY STATE, COUNTY, OR LOCAL OFFICIALS. 2. ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED IN THE FIELD BY THE
- 3. CONSTRUCTION STAGING AREA (TO BE DETERMINED BY CONTRACTOR) SHALL INCLUDE THE
- NOI POSTING, PORT-O-LETS, TRASH CONTAINERS, AND FUELING TANKS. CONTRACTOR SHALL NOT LOCATE STAGING AREA WITHIN PROPOSED PARKING LOT.
- 4. A TRAINED INDIVIDUAL MUST PERFORM AN INSPECTION ONCE A WEEK AND AFTER EVERY 1/2" OR MORE RAIN EVENT. A LOG OF THE INSPECTION REPORTS MUST BE KEPT AND MADE AVAILABLE TO THE CITY INSPECTOR UPON REQUEST.
- 5. THERE SHALL BE NO DIRT, DEBRIS, OR STORAGE OF MATERIALS WITHIN THE EXISTING STREET OR RIGHT-OF-WAYS, OR PROPOSED PARKING AREAS.

 6. ALL EROSION CONTROL PRACTICES SHALL BE IN ACCORDANCE WITH THE INDIANA STORM
- WATER QUALITY MANUAL AND THE S.C.S. "FIELD OFFICE TECHNICAL GUIDE".
 7. ALL STORM WATER CASTINGS SHALL BE PHASE II COMPLIANT. 8. CONTRACTOR SHALL UTILIZE 12 OZ/SQ. YD. MINIMUM WEIGHT, NON-WOVEN NEEDLE
- PUNCHED GEOTEXTILE FABRIC BENEATH ALL RIPRAP USED FOR OUTLET PROTECTION.

 9. ALL PORT—O—LETS MUST BE ANCHORED DOWN TO PREVENT SPILLS.

 10. THE CITY ENGINEER HAS THE RIGHT TO REQUIRE ADDITIONAL EROSION CONTROL MEASURES IN THE FIELD AS CONTROL MEASURES IN THE FIELD AS CONTROL
- 11. THE TRAINED INDIVIDUAL RESPONSIBLE FOR ALL EROSION CONTROL MEASURE INSTALLATION AND MAINTENANCE IS: KEVIN WALLS, JOHNSON COUNTY BOARD OF COMMISSIONERS, PHONE: (317) 346–4306, EMAIL: kwalls@co.johnson.in.us



KEYMAP NO SCALE

ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED BY STATE, CITY OR COUNTY OFFICIALS

<u>NOTE:</u> NO EARTHWORK DISTURBING ACTIVITY MAY COMMENCE UNTIL A STORM WATER MANAGEMENT PERMIT IS OBTAINED.

ISSUE DATE 2301301 8-30-2024 SUBMITTAL 100% Construction Document Set

EROSION CONTROL

ELEVATUS ARCHITECTURE 111 E. Wayne Street, Suite 555, Fort Wayne, IN 46802 260 424-9080 ElevatusArchitecture.com CONFIDENTIAL COPYRIGHT 2024 S2 ARCHITECTS, LLC dba ELEVATUS ARCHITECTURE

SZ ARCHITECTS, LLC GDA ELEVATUS ARCHITECTURE

PURSUANT TO SECTION 1920 FTHE COPYRIGHTA ACT, 17 U.S.C., ALL CONCEPTS, IDEAS

DESIGNS, ARRANGEMENTS, DRAWINGS, AND PLANS INDICATED OR REPRESENTED BY

THIS DOCUMENT ARE COPYRIGHTED BY SZ ARCHITECTS, LLC dBa ELEVATUS

ARCHITECTURE, AS SUCH ALL CONCEPTS, IDEAS, DESIGNS, ARRANGEMENTS,

DRAWINGS, AND PLANS INDICATED OR REPRESENTED BY THIS DOCUMENT ARE OWN

BY AND THE PROPERTY OF SZ ARCHITECTS, LLC dBa ELEVATUS ARCHITECTURE AND

WERE CREATED, EVOLVED AND DEVELOPED FOR ITS OWN USE. NONE OF THE IDEAS,

DESIGNS, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY

PERSON, ARCHITECTURAL OR ENGINEERING FIRM, CONSTRUCTION FIRM.


SUBCONTRACTING FIRM, SUPPLIER, OR CORPORATION FOR ANY PURPOSE WHATSOE

WITHOUT THE WRITTEN PERMISSION OF SZ ARCHITECTS, LLC GBS ELEVATUS

ARCHITECTURE.

STATE AND LOCAL LAWS.

WRITTEN DIMENSIONS ON THESE DOCUMENTS SHALL HAVE PRECEDENCE OVER SCALE
DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSION
AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATION
FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP
DRAWINGS AND OR DETALS MUST BE SUBMITTED TO THIS OFFICE FOR REVIEW BEFOR
PROCEEDING WITH FABRICATION.





County Court Sand Road Road Road Franklin, IND

REVISIONS DESCRIPTION

The construction limits (boundary of disturbed area) are shown on the Erosion Control Plan. PROPOSED STORMWATER SYSTEMS

The proposed stormwater system sizes and dimensions are labeled on the Erosion Control Plan. PROPOSED STORMWATER DISCHARGE Proposed stormwater will discharge into the existing and proposed storm sewer systems before discharging into the creek at the south end of the site.

ECPC-801-C-8

ECPC-801-C-8

ECPC-801-C-8

ECDC-803

ECDC-803

B12

B14

ECDC-803

ECDC-803

ECPC-801-C-8

ECPC-801-C-8

All site improvements are shown on the Erosion Control Plan. SOIL STOCKPILES, BORROW/DISPOSAL AREAS

Topsoil shall be stockpiled in a convenient location (as determined by the owner and/or contractor) within the construction site as shown on the Erosion Control Plan. CONSTRUCTION SUPPORT ACTIVITIES There are no construction support activities anticipated with these improvements.

A culvert crossing will be constructed to complete the drive crossing over the unnamed tributary

STORMWATER POLLUTION PREVENTION - DURING CONSTRUCTION

POTENTIAL POLLUTANT SOURCES ASSOCIATED WITH CONSTRUCTION ACTIVITIES There is a potential for pollutants associated with construction machinery including diesel fuel, hydraulic fluid, engine oils and lubricants, antifreeze and other petroleum products. It is unavoidable for a small amount of these pollutants to contaminate soil in the grading and construction of the

The construction entrance shall be constructed in the northern section of the project off of Hospital Road. Specifications and details are located on the Stormwater Pollution Prevention Plan. TEMPORARY & PERMANENT STABILIZATION

Temporary & Permanent surface stabilization methods are shown on the Erosion Control Plan and detailed on the Stormwater Pollution Prevention Plan SEDIMENT CONTROL MEASURES FOR CONCENTRATED FLOW AREAS

Sediment Control measures for concentrated flow areas are shown on the Erosion Control Plan. Specifications and details are located on the Stormwater Pollution Prevention Plan. SEDIMENT CONTROL MEASURES FOR SHEET FLOW AREAS

Sediment Control measures for Sheet flow areas are shown on the Erosion Control Plan. Specifications and details are located on the Stormwater Pollution Prevention Plan.

RUNOFF CONTROL MEASURES Runoff control measures are shown on the Erosion Control Plan. Specifications and details are located on the Stormwater Pollution Prevention Plan.

STORMWATER OUTLET PROTECTION MEASURES Stormwater outlet protection measures are shown on the Erosion Control Plan. Specifications and details are located on the Stormwater Pollution Prevention Plan. GRADE STABILIZATION STRUCTURES

No grade stabilization structures are required for this project DEWATERING ACTIVITIES If required during excavation operations, dewatering shall be completed as shown on the Erosion

Control Plan. Specifications and details are located on the Erosion Control Plan and Stormwater Pollution Prevention Plan WATERBODY QUALITY MEASURES

Measures utilitized for work within waterbodies are shown on the Erosion Control Plan and associated details/specifications are shown on the Stormwater Pollution Prevention Plan. MONITORING AND MAINTENANCE GUIDELINES Monitoring and Maintenance Guidelines are located in the middle on the Stormwater Pollution

Prevention Plan PLANNED CONSTRUCTION GUIDLINES Planned Construction Sequence guidelines are located in the middle on the Stormwater Pollution

Prevention Plan.

EROSION & SEDIMENT CONTROL MEASURES FOR INDIVIDUAL BUILDING LOTS

Not applicable, as this is to be developed as a single site/property. MATERIAL HANDLING AND SPILL PREVENTION

Spill prevention shall be accomplished by utilizing spillguards for equipment fueling and servicing operations. Spillquards shall be 3'x3'x6" and shall be constructed of a material resistant petroleum products (including diesel fuel and oil). On—site fuel storage tanks shall have emergency storage capacity directly below the tank in case of rupture. Any hazardous material spillage shall be

federal, state and local regulations Indiana Department of Environmental Management Office of Emergency Response (317) 233-7745, Toll Free (800) 233-7745

collected and/or cleaned immediately by a trained individual and disposed of in accordance with all

Franklin Fire Department (317) 736-3651 *Additional Material Handling and Spill Prevention (this sheet)* MATERIAL HANDLING AND STORAGE Material Handling and Storage Procedure guidelines are located in the middle on the Stormwater

Pollution Prevention Plan.

STORMWATER POLLUTION PREVENTION - POST CONSTRUCTION

PROPOSED POST CONSTRUCTION STORMWATER MEASURES.

PROPOSED POLLUTANTS AND SOURCES ASSOCIATED WITH PROPOSED LAND USE Potential pollutants include petroleum products and antifreeze from automobiles using the parking areas and sediment.

Post construction stormwater quality measures shall consist of two mechanical water quality units. LOCATION, DIMENSIONS, SPECIFICATIONS AND DETAILS OF EACH STORMWATER QUALITY MEASURE The location of the mechanical water quality units is shown on the construction plans.

STORMWATER QUALITY MEASURE IMPLEMENTATION Stormwater quality measures are implemented by construction of the site improvements which include A. PURPOSE installation of the mechanical water quality units for stormwater quality treatment.

MAINTENANCE GUIDELINES OF POST CONSTRUCTION STORMWATER QUALITY MEASURES All landscape areas shall be maintained by mowing, removing trash and debris, and re-planting any vegetated areas as necessary. The proposed storm sewer inlets shall be inspected for blockage of any type after each storm event. All obstructions, trash, and debris shall be removed upon inspection. Maintenance and inspection of the mechanical water quality units shall be performed in accordance with the manufacturer's recommendation ands the Operations and Maintenance (0&M) Manual approved by the City of Franklin.

PARTY RESPONSIBLE FOR POST-CONSTRUCTION STORMWATER POLLUTION PREVENTION Owner: Johnson County, Kevin Walls, Phone: (317) 346-4306, Email: kwalls@co.johnson.in.us

GRAVEL CONSTRUCTION DRIVE AND PARKING AREA: A. Inspect daily and after each storm event. Immediately remove mud and sediment tracked or washed

onto public roads. Top dress with clean aggregate as needed. Reshape pad as needed for drainage and runoff control. Flushing should only be used if the water can be conveyed into a sediment trap or basin.

Inspect daily until vegetation is established. B. Check for erosion or damage of newly spread topsoil and repair immediately.

recommendations.

The Legal Description of the project site is located in the lower right quadrant of the Stormwater <u>TEMPORARY AND PERMANENT SEEDING:</u> A. Inspect seeding within 24 hours of each rain event and at least once every seven calendar days $^{
m C}.$ until vegetation is established.

Check for erosion or movement of mulch and repair immediately Plan to add fertilizer the following growing season according to soil test recommendations. Repair damaged, bare, or sparse areas by filling any gullies, re-fertilizing, over- or re-seeding, and

If plant cover is sparse or patchy, review the plant materials chosen, soil fertility, moisture condition, and mulching; repair the affected area either by over—seeding or by re—seeding and mulching after re-preparing the seed bed. If vegetation fails to grow, consider soil testing to determine acidity or nutrient deficiency problems. If additional fertilization is needed to get a satisfactory stand, do so according to soil test

H. Reference INDOT Specification 621.05

EROSION CONTROL BLANKET: A. Inspect within 24 hours of each rain event and at least once every seven calendar days. Check for erosion or displacement of the blanket. B. If any area shows erosion, pull back that portion of the blanket covering the eroded area, add soil

and tamp, re—seed the area, and re—lay and staple the blanket. After vegetative establishment, check the treated area periodically.

A. Inspect within 24 hours of each rain event to check for movement of mulch or for erosion. B. If washout, breakage, or erosion is present, repair damage areas, re—seed, apply new mulch, and

Continue inspections until vegetation is firmly established. Reference INDOT Specification 621.05

A. Inspect periodically for displaced rock material, slumping, and erosion at edges, especially downstream or downslope

. Inspect within 24 hours of each rain event and at least once every seven calendar days. B. If fence fabric tears, starts to decompose, or in any way becomes ineffective, replace the affected portion immediately. Remove deposited sediment when it reaches half the height of the fence at its lowest point or is

causing the fabric to bulge. Take care to avoid undermining the fence during clean out. After the contributing drainage area has been stabilized, remove the fence and sediment deposits, bring the disturbed area to grade and stabilize.

SILT SACK INLET PROTECTION: A. Inspect the silt sack inlet protection periodically and after each $\frac{1}{2}$ " storm event.

Remove deposited sediment when it reaches half the height of the filter at the lowest point. Remove the Silt Sack Inlet Protection and sediment deposits after contributing drainage area is

FABRIC DROP INLET PROTECTION:

Inspect the fabric barrier after storm events, and make needed repairs immediately.

undercutting the fabric during sediment removal. When the contributing drainage area has been stabilized, remove and properly dispose of all construction material and sediment, grade the area to the elevation of the top of the inlet, then

Concrete washout area shall be installed prior to any concrete placement on site.

. Signs shall be placed at the construction entrance, at the washout area, and elsewhere as necessary to clearly indicate the location of the concrete washout area to operators of concrete trucks and pump rigs. The concrete washout area shall be repaired and enlarged or cleaned out as necessary to maintain

capacity for wasted concrete. D. At the end of construction, all concrete shall be removed from the site and disposed of at an approved waste site.

When the concrete washout area is removed, the disturbed area shall be seeded and mulched or otherwise stabilized in a manner approved by the inspector.

CONSTRUCTION SEQUENCE & SCHEDULE OF EROSION CONTROL IMPLEMENTATION

Silt fence and/or straw bales shall be placed around existing structures and in ditches as shown in these plans before any land disturbing activities are started Schedule a pre—construction meeting with the City of Franklin 48 hours prior to start of earthwork. Construct temporary gravel entrance in accordance with the "INDIANA STORM WATER QUALITY MANUAL". All other erosion control measures and detention areas shall be installed and constructed

Construct detention pond and install respective outlet structures. Strip topsoil and stockpile as shown. Rough grade site. Disturbed areas should be seeded immediately following rough grading. Areas that will not be disturbed again should be permanently seeded. No unvegetated areas should be exposed

as shown at the beginning of the project.

Place drainage structures. Erosion control measures shall be placed around proposed structures as soon as they are in place and until vegetation is secure.

8. Final grade site. All erosion control blankets shall be installed per manufacturers recommendations as soon as final grading is complete

9. Final paving operations. Temporary erosion control measures shall remain in place until vegetation is

GENERAL EROSION CONTROL REQUIREMENTS FOR COMPLIANCE WITH IDEM GENERAL PERMIT RULES FOR STORM WATER RUNOFF FROM CONSTRUCTION SITES

All Erosion Control practices shall be in accordance with the latest edition of the INDIANA STORM WATER QUALITY MANUAL.

The Erosion Control measures included in this plan shall be installed prior to initial land disturbance activities or as soon as practical. Sediment shall be prevented from discharging from the project site by installing and maintaining silt fence, straw bales, sediment basins, etc. As shown on this plan. If shown on this plan, energy-dissipation devices or Erosion Control at the outfall of the storm sewer

3. All on-site storm drain inlets shall be protected against sedimentation with silt sack inlet filters, filter fabric, or equivalent barriers as shown on this plan.

system shall be installed at the time of the construction of the outfall.

4. Except as prevented by inclement weather conditions or other circumstances beyond the control of the contractor/developer appropriate Erosion Control practices will be initiated within (7) seven days of the last land disturbing activity at the site. The site shall be stabilized by seeding, sodding, mulching, covering, or by other equivalent Erosion Control measures.

This Erosion Control plan shall be implemented on all disturbed areas within the construction site. All measures involving Erosion Control practices shall be installed under the guidance of a qualified person experienced in Erosion Control and following the plans and specifications included herein.

6. During the period of construction activity, all sediment basins and other Erosion Control measures shall be maintained by the contractor. At the completion of construction, the contractor shall coordinate the transfer of required maintenance responsibilities with the owner.

. Public or private roadways shall be kept cleared of accumulated sediment. Bulk clearing of accumulated sediment shall not include flushing the area with water. Cleared sediment shall be returned to the point of likely origin or other suitable location.

8. The contractor shall control wastes, garbage, debris, wastewater, and other substances on the site in such a way that they shall not be transported from the site by the action of winds. The following steps will help keep a clean site and reduce stormwater pollution: storm water runoff, or other forces. Proper disposal or management of all wastes and unused building materials appropriate to the nature of the waste or material is required.

9. Additional Erosion Control measures may be required by state or county agencies

ADDITIONAL MATERIAL HANDLING AND SPILL PREVENTION PLAN

The purpose of this plan is two fold: To help protect the health and safety of those working on the site as well as the environment. . Preventing the contamination of storm water runoff. Pollutants generated onsite may include gasoline, diesel fuel, oils, grease, paints, pesticides, nutrients, concrete washout, soil, solvents, paper, plastic, Styrofoam, metals, glass and other forms of liquid or solid wastes. This plan outlines procedures to help prevent health and safety issues, contamination of storm water by onsite pollutants, help prevent fuel and chemical spills and provide a response procedure should a

• Arrange for regular waste collection before containers overflow

PREVENTION AND READINESS

SPILL RESPONSE

properly.

. The contractor or responsible party will prepare a contact list in the event of a spill on the site. The contact list will have names and contact numbers. The contact list will specify first responders and a chain of command. Include information on what circumstances require the initiation of the contact list and chain of command.

2. The contractor/owner shall maintain a list of qualified contractors, Vac-trucks, tank pumpers and other equipment or businesses qualified to do clean-up operations. Absorbent materials and supplies need to be available onsite in sufficient quantities to address minor spills. All employees need to be educated on the proper application of the absorbent materials.

continuing education program is required for new employees and emphasizing the importance to all employees. 4. All materials used in the course of a cleanup will be disposed in a manor approved by Indiana Department of Environmental Management.

5. Using water to flush spilled material will not be permitted unless authorized by a state, federal, or local agency. Tarps can be used to cover spilled material during rain events.

Minor - Small spills that typically involve oil gasoline, paint, hydraulic fluid etc. Minor spills can be controlled by the first responder at the discovery of the spill. · Contain spill to prevent material from entering storm or ground water. Do not flush with water o • Use absorbent material to clean-up spill material and any subsequently contaminated soil and dispose of

Semi-significant Spills - Approximately ten gallons or less of pollutant with no contamination of ground or surface waters. Minor spills can be generally controlled by the first responder with help from other site personnel. This response may require other operations to stop to make sure the

• Do no allow excess concrete to be dumped onsite, except in designed areas. spill is quickly and safely addressed. At the discovery of the spill: · Contain spill to prevent material from entering storm or ground water. Do not flush with water or · Use absorbent material to clean-up spills and dispose of properly. Spills on impervious surfaces should be contained with a dry absorbent. Spills on clayey soils should be contained by

deeper into the soil and groundwater. Dispose of contaminated soils or absorbents properly.

• Contact 911 if this spill could be a safety issue. Contact supervisors and designated inspectors immediately Contaminated solids to be removed to an approved landfil

Major or Hazardous Spills — More than ten gallons, there is the potential for death, injury or illness to humans or animals or has the potential for surface or groundwater pollution. • Control or contain the spill without risking bodily harm. Temporarily plug storm drains if possible to prevent migration of the spill into the stormwater system. • Immediately contact the local Fire Department at 911 to report any hazard material spill.

constructing an earthen dike and should be disposed of as soon as possible to prevent migration

• Contact supervisors and designated inspectors immediately. Other county or municipal officials (list as needed) responsible for storm water facilities should be contacted as well. The contractor facility with an impervious floor. is responsible for having these contact numbers available at the job site. A written report should

• Use a dedicated site for machinery maintenance be submitted to the owner as soon as possible. • As soon as possible but within 2 hours of discovery, contact the Department of Environmental Management,

Office of Emergency Response 1-888-233-7745. The following information should be reports to IDEM or the National Response Center. o Name, address and phone number of person making the spill report

o Identification of the spilled substance o Approximate quantity of the substance that has been spilled or may be further o The duration and source of the spill o Name and location of the damaged waters

o The location of the spill

o The time of the spill

o Name of spill response organization What measures were taken in the spill response o Other information that may be significant Additional regulation or requirements may be present. A spill response professional should be

consulted to make sure all appropriate and required steps have been taken. Contaminated solids

No washout of solvent from paint supplies should be done near or into a storm water inlet should only be removed from the site after approval is given by Emergency Response.

Remove sediment from the pool area to provide storage for the next storm. Avoid damaging or D. THE FOLLOWING PROCEDURES AND PRACTICES WILL HELP PREVENT UNNECESSARY SPILLS

I. Vehicle and Equipment Fueling

Description and Purpose: Vehicle equipment fueling procedures and practices are designed to prevent fuel spills and leaks, and reduce or eliminate contamination of stormwater. This can be accomplished by using offsite facilities, fueling in designated areas only, enclosing or covering stored fuel, implementing spill A suitable practice is needed at the discharge to allow the suspended solids to be removed. controls, and training employees and subcontractors in proper fueling procedures.

• Onsite vehicle and equipment fueling should only be used where it is impractical to send vehicles • Sediment removal pumping bags may be used at the outlet of a pump. The bags must be and equipment offsite for fueling.

• Use offsite fueling stations as much as possible. These businesses are better equipped to handle • Pumping operations that are moving clean water through a site are not required to have a fuel and spills properly. Performing this work offsite can also be economical by eliminating the need for a separate fueling area at a site. Discourage "topping—off" of fuel tanks. Absorbent spill cleanup materials and spill kits should be available in fueling areas and on fueling

trucks, and should be disposed of properly after use. • Drip pans or absorbent pads should be used during vehicle and equipment fueling, unless the fueling is performed over an impermeable surface in a dedicated fueling area. • Use absorbent materials on small spills. Do not hose down or bury the spill. Remove the absorbent materials promptly and dispose of properly. · Avoid mobile fueling of mobile construction equipment around the site; rather, transport the equipment to designated fueling greas. Train employees and subcontractors in proper fueling and cleanup procedures.

• Dedicated fueling areas should be protected from stormwater run—on and runoff, and should be located at least 50 feet away from the downstream drainage facilities and watercourses. Fueling must be performed on level—grade areas. Protect fueling areas with berms and dikes to prevent run—on, runoff, and to contain spills. Nozzles used in vehicle and equipment fueling should be equipped with an automatic shutoff to

control drips. Fueling operations should not be left unattended. Federal, state, and local requirements should be observed for any stationary above ground storage tanks.

Inspection and Maintenance Vehicles and equipment should be inspected each day of use for leaks. Leaks should be repaired immediately or problem vehicles or equipment should be removed from the project site. • Keep ample supplies of spill cleanup materials onsite.

• Immediately clean up spills and properly dispose of contaminated soils.

II. Solid Waste Management

package construction materials.

• Solid waste management procedures and practices are designed to prevent or reduce the discharge of pollutants to stormwater from solid or construction waste by providing designated waste collection areas and containers, arranging for regular disposal, and training employees and subcontractors.

This BMP is suitable for construction sites where the following wastes are generated or stored: Solid waste generated from trees and shrubs removed during land clearing, demolition of existing structures (rubble), and building construction.

• Packaging materials including wood, paper, and plastic. • Scrap or surplus building materials including scrap metals, rubber, plastic, glass pieces, and masonry products. Domestic wastes including food containers such as beverage cans, coffee cups, paper bags, plastic wrappers, and cigarettes Construction waste including brick, mortar, timber, steel and metal scraps, pipe and electrical cuttings, non—hazardous equipment parts. Styrofoam and other materials send transport and

• Select designated waste collection areas onsite.

• Inform trash-hauling contractors that you will accept only watertight dumpsters for onsite

• Inspect dumpsters for leaks and repair any dumpster that is not watertight. • Provide an adequate number of containers with lids or covers that can be placed over the container to keep rain out or to prevent loss of wastes when it is windy. Plan for additional containers and more frequent pickup during the demolition phase of construction.

• Collect site trash daily, especially during rainy and windy conditions. Remove this solid waste promptly since erosion and sediment control devices tend to collect · Make sure that toxic liquid wastes (used oils, solvents, and paints) and chemicals (acid,

pesticides, additives, curing compounds) are not disposed of in dumpsters designed for construction debris. • Do not hose out dumpsters on the construction site. Leave dumpster cleaning to the trash

• Make sure that construction waste is collected, removed, and disposed of only at authorized disposal areas. Solid waste storage areas should be located in areas prone to flooding or Locate solid waste dumpster a minimum of 50' away from storm water inlets or other drainage facilities. · Locate dumpster on stone or earth to minimize the potential for spills or leaks to drain immediately into a drainage facility.

Inspection and Maintenance: • Inspect and verify that activity-based BMPs are in place prior to the commencement o 3. All maintenance and equipment operators must be aware and trained for prevention of spills. A associated activities. While activities associated with the BMP are under way, inspect weekly to verify continued BMP implementation. • Inspect BMPs subject to non-stormwater discharge daily while non-stormwater discharges

> Inspect construction waste are regularly. Arrange for regular waste collection.

• Clean up immediately if a container does spill.

III. Concrete Washout

The following steps will help reduce stormwater pollution from concrete wastes:

• Discuss the concrete management techniques described in the BMP (such as handling of concrete waste and washout) with the reddy-mix concrete supplier before any deliveries are Incorporate requirements for concrete waste management into material supplier and

subcontractors' agreements. • Store dry and wet materials under cover, away from drainage areas. Avoid mixing excess amounts of fresh concrete.

 Perform washout of concrete trucks offsite or in designed areas only. Do not wash concrete trucks into storm drains open ditches, streets, or streams.

 Locate washout areas at least 50 feet from storm drains, open ditches, or water bodies. Do not allow runoff from this area by constructing a temporary pit or bermed area large enough for liquid and solid waste. • Wash out wastes into the temporary pit where the concrete can set, be broken up, and then disposed properly. Avoid creating runoff by drinking water to a bermed or level area when washing concrete to remove fine particles and expose the aggregate.

V. Vehicle Maintenance Areas

Collect and return sweepings to aggregate base stockpile or dispose in the trash.

Purpose— To prevent spills during the normal maintenance of construction machinery. Implementation— Where and when feasible, maintenance shall be preformed offsite in covered

• Do not wash sweepings form exposed aggregate concrete into the street or storm drain.

Site the maintenance area at least 50 feet from storm water inlets or water bodies • Maintain clean up materials close at hand. Utilize drip pans and absorbent pads to preve oils from reaching the soil surface.

Inspect equipment daily for leaks or worn hoses. Repair or replace to prevent onsite spills Properly dispose of all fluids removed or spilled from machinery. V. Fluids, paints, solvents and other chemicals storage and use

Purpose— To prevent spills during the use and storage of the materials

Implementation-• Store materials in there original containers Maintain safety data sheets on all products • Store materials in a weather proof/vandal resistant locker or building

 Keep materials away from flammable sources Provide and read instructions for the proper use and storage of all materials • For bulk material stored onsite, provide diking or double containment in case of leaks or

VI. Disposal of sediment laden water Purpose— To prevent the purposeful discharge of sediment laden water into waters of the United

• The sediment and any other pollutant from all pumping or dewatering operations that discharge into storm sewers, wetlands, drainage ways or water bodies must be removed from the water before it's discharged

3:1 2:1 1:1

SLOPE GRADIENT

EROSION CONTROL BLANKE

STAPLE PATTERN DETAIL

SPECIES | SEEDING RATE | SUITABLE PH | SITE SUITABLE PH | DROUGHTY | DRA

1-PREFERRED 2-WILL TOLERATE ** - INOCULATE WITH SPECIFIC INOCULATES

35 5.5 - 8.3 2 1 2

1.5 STAPLES PER SYD

TALL FESCUE RED CLOVER **

KENTUCKY BLUEGRASS

PERENNIAL RYEGRASS (TURF TYPE)

TALL FESCUE EMERALD CROWNVETCH **

from the water column. Slow moving water and time are needed components for an effective practice. Mechanical filters and chemical flocculants can do an excellent job of removing the fine materials. sized appropriately for the amount of flow. The practice needs to be installed on erosion

resistant surfaces. The outlet of the pumping bag must be erosion resistant to prevent additional sedimentation. pumping bag or similar device at the outlet. The point of discharge should be protected to

20" — * *

KENTUCKY BLUEGRASS POA PROTINSIS

CORANILLA VARIA

D CLOVER TRIFOLIUM PRATENSE


WHEAT OR RYE

SPRING OATS

ANNUAL RYEGRASS

NON-IRRIGATED *

TALL FESCUE FESTUCA L ARUNDINACEA



Johnson County, Indiana (IN081)

moderately well drained but still has a frequent chance flooding.

| MED. 1 20-25 12-18 7-21 |

MED. 1 25-35 12-18 10-20

1 |LOW| 1 |24-35|24-36|5-14

2 MED- 2 15-20 12-18 5-10

- LOW 1 5-10 24 14-21 T

T TOLERANCE (TO BOTH SOIL SALTS AND SPRAY)

| - | 2 | - | - | MED. | 1 | 7-10 | 18 | 5-10 | S | S |

NPPLY LIME TO RAISE THE pH TO THE LEVEL NEEDED FOR SPECIES BEING SEEDED. APPLY 23

MMONIUM NITRATE ON AREAS LOW IN ORGANIC MATTER AND FERTILITY WILL GREATLY ENHANCE

INCHES WITH A HARROW, DISK, OR RAKE OPERATED ACROSS THE SLOPE AS MUCH AS POSSIBIL

ERTILIZER AND LIME SHALL MEET REQUIREMENTS OF INDOT STANDARD SPECIFICATIONS 1995.

<u>SEEDING</u> SELECT A SEED MIXTURE BASED ON PROJECTED USE OF THE AREA WHILE CONSIDERING BEST

IRRIGATION NEEDED DURING THIS PERIOD. TO CONTROL EROSION AT TIMES OTHER THAN IN THE SHADED AREAS.

** HNCREASE SEEDING APPLICATION BY 50%.

TEMPORARY SEEDINGS
PER 1,000 SQ. FT. PER ACRE REMARKS

* NOT NECESSARY WHERE MULCH IS APPLIED

* -LATE SUMMER SEEDING DATES MAY BE EXTENDED 5 DAYS IF MULCH IS APPLIED.

LBS. OF 12-12-12 ANALYSIS FERTILIZER (OR FOLIVALENT) PER 1,000 SQ. FT. (APPROXIMATEL)

1.000 LBS. PER ACRE) OR FERTILIZE ACCORDING TO TEST. APPLICATION OF 150 LBS. OF

VEGETATIVE GROWTH. WORK THE FERTILIZER AND LIME INTO THE SOIL A DEPTH OF 2 TO 3

URBAN LAND-CROSBY SILT LOAM COMPLEX (UcfA) This nearly level mapping unit is on smooth recessionial, gorund, and water—lain moraines . Slopes are 0 to 2 percent. Runoff is generally rapid on the Urban land and slow on the Crosby soils. Wetness and slow permeability the Crosby soils have severe limitations for most non-farm uses.


URBAN LAND-MIAMI COMPLEX SILT LOAM COMPLEX, Eroded (UkbB2) iis moderately sloping mapping unit is along till plain shoulders, backslopes, and footslopes. Slopes are 2 to 6 percent. Runoff is generally rapid on the Urban soils

and medium on the Miami soils. URBAN LAND-MIAMI CLAY LOAM COMPLEX, Severly Eroded (UmcD3)

This heavily sloping mapping unit is along the shoulders and backslopes of moraines and till plains. Slopes are 12 to 18 percent. Runoff is generally rapid on the Urban soils and slow on the Fox soils. EEL SILT LOAM, URBAN LAND COMPLEX, Frequently Flooded-Brief Duration (YcIAH)

This nearly level soil is typically found in flood plains and flood plain treads. Slopes are 0 to 2 percent. Runoff is generally low on soils of this type. Land is

SOIL MAP AND DESCRIPTION



VICINITY MAP NOT TO SCALE

LEGAL DESCRIPTION

DEED BOOK 027, PAGE 245
A PART OF THE NORTH HALF OF THE WEST HALF OF THE NORTHEAST QUARTER OF SECTION 22, TOWNSHIP NORTH, RANGE 4 EAST, CONTAINING 40 ACRES MORE OR LESS;

ALSO A PART OF ALL THAT PART OF THE WEST HALF OF THE SOUTHEAST QUARTER OF SECTION 15, TOWNSHIP 1 NORTH, RANGE 4 EAST THAT LIES SOUTH OF THE FRANKLIN & HOPEWELL GRAVEL ROAD, EXCPET A SMALL TRACT IN THE NORTHWEST CORNER THEREOF ON WHICH THE FORMER TOLL HOUSE WAS AND IS LOCATED, CONTAINING IN ALL 60 ACRES; EXCEPTING THEREFROM 30 ACRES BY PARALLEL LINES OFF OF THE EAST SIDE, ENTIRE LENGTH

ADDITIONAL FROSION CONTROL MEASURES MAY BE REQUIRED BY STATE OR COUNTY OFFICIALS

ISSUE DATE 2301301 8-30-2024 SUBMITTAL 100% Construction Document Set

ELEVATUS

ARCHITECTURE

111 E. Wayne Street, Suite 555, Fort Wayne, IN 46802

PURSUANT TO SECTION 102 OF THE COPYRIGHT ACT, 17 U.S.C., ALL CONCEPTS, ID DESIGNS, ARRANGEMENTS, DRAWINGS, AND PLANS INDICATED OR REPRESENTED THIS DOCUMENT ARE COPYRIGHTED BY 52 ARCHITECTS, LIC das ELEVATUS ARCHITECTURE. AS SUCH ALL CONCEPTS, IDEAS, DESIGNS, ARRANGEMENTS, DRAWINGS, AND PLANS INDICATED OR REPRESENTED BY THIS DOCUMENT ARE OV

BY AND THE PROPERTY OF SZ ARCHITECTS, LLC dab. ELEVATUS ARCHITECTURE AND WERE CREATED, EVOLVED AND DEVELOPED FOR ITS OWN USE. NOR BOTH TO BE DESIGNS, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, ARCHITECTURAL OR ENGINEERING FRM. CONSTRUCTION FIVE SUBCONTRACTION FROM SUPPLIER, OR CORPORATION FOR ANY PURPOSE WHATSO SUBCONTRACTION FOR ANY PURPOSE WHATSO

PURSUANT TO SECTION 102 OF THE COPYRIGHT ACT, 17 U.S.C., PROTECTION FOR AN ARCHITECTURAL WORK CREATED AS A WORK MADE FOR HIRE ON OR AFTER DECEM

AMOUNT LEV LIVEAL WORK CREAT IELD AS A WORK MADE FOR HIRE ON OR AFTER DECEM. 1, 1990, LASTS FOR 95 YEARS FROM THE DATE OF PUBLICATION OF THE WORK OR FO. 120 YEARS FROM THE DATE OF CREATION OF THE UNPUBLISHED PLANS, WHICHEVER TERM IS LESS.

HEMMIS LESS.

WARNIN: REPRODUCTION HEREOF IS A CRIMINAL OFFENSE UNDER SECTION 102 OF T COPYRIGHT ACT, 17 U.S.C., 18 U.S.C., SEC. 506. UNAUTHORIZED DISCLOSURE MAY CONSTITUTE TRADE SECRET MISAPPROPRIATION IN VIOLATION OF IC.242-31-1ET, SEC AND OTHER LAWS. THE CONCEPTS, IDEAS, DESIGNS, ARRANGEMENTS, DRAWINGS, AN PLANS DISCLOSED ARE COPYRIGHTED AND HEREIM MAY BE PATENTED OR BE THE SUBJECT OF PENDING PATENT APPLICATION, ANYONE VIOLATING THE INTENT OF THIS COPYRIGHT PROTOCTION WILL BE PROSECUTED TO THE FULL EXTENT OF THE FEDERA STATE AND LOCAL LAWS.

WRITTEN DIMENSIONS ON THESE DOCUMENTS SHALL HAVE PRECEDENCE OVER SCAL DIMENSIONS, CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATION FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS, SHOP DRAWINGS AND OR DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR REVIEW BEFO PROCEEDING WITH FABRICATION.

REGISTERED

No. 12400527

STATE OF

MOIANA

a

0

AD

O O

0

ohn

REVISIONS


DESCRIPTION


ITHOUT THE WRITTEN PERMISSION OF S2 ARCHITECTS, LLC dba ELEV RCHITECTURE.


S2 ARCHITECTS, LLC dba ELEVATUS ARCHITECTURE


ElevatusArchitecture.com

260 424-9080












CONFIDENTIAL COPYRIGHT 2024

\$2 ARCHITECTS, LLC dba ELEVATUS ARCHITECTURE

PURSUANT TO SECTION 102 OF THE COPYRIGHT ACT, 17 U.S.C., ALL CONCEPTS, IDEAS, DESIGNS, ARRANGEMENTS, DRAWINGS, AND PLANS INDICATED OR REPRESENTED BY THIS DOCUMENT ARE COPYRIGHTED BY \$2 ARCHITECTS, LLC dba ELEVATUS ARCHITECTURE. AS SUCH ALL CONCEPTS, IDEAS, DESIGNS, ARRANGEMENTS, DRAWINGS, AND PLANS INDICATED OR REPRESENTED BY THIS DOCUMENT ARE OWNED BY AND THE PROPERTY OF SEARCHITECTS, LLC dba ELEVATUS ARCHITECTURE AND WERE CREATED, EVOLVED AND DEVELOPED FOR ITS OWN USE. NONE OF THE IDEAS, DESIGNS, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, ARCHITECTURAL OR ENGINEERING FIRM, CONSTRUCTION FIRM. SUBCONTRACTING FIRM, SUPPLIER, OR CORPORATION FOR ANY PURPOSE WHATSOEV WITHOUT THE WRITTEN PERMISSION OF \$2 ARCHITECTS, LLC dba ELEVATUS ARCHITECTURAL WORK CREATED AS A WORK MADE FOR HIRE ON OR AFTER DECEMBE 1,1990. LASTS FOR 95 YEASTS FROM THE DATE OF PUBLICATION OF THE WORK OR FOR 120 YEARS FROM THE DATE OF PUBLICATION OF THE WORK OR FOR 120 YEARS FROM THE DATE OF PUBLICATION OF THE WORK OR FOR 120 YEARS FROM THE DATE OF PUBLICATION OF THE WORK OR FOR 120 YEARS FROM THE DATE OF PUBLICATION OF THE WORK OR FOR 120 YEARS FROM THE DATE. OF PUBLICATION OF THE WORK OR FOR 120 YEARS FROM THE DATE OF PUBLICATION OF THE WORK OR FOR 120 YEARS FROM THE DATE OF PUBLICATION OF THE WAS AND THE DATE OF CREATION OF SACRUMANDAY. WHICHEVER TERM IS LESS.

WARNIN: REPRODUCTION HEREOF IS A CRIMINAL OFFENSE UNDER SECTION 102 OF T COPYRIGHT ACT, 17 U.S.C.; 18 U.S.C. SEC. 550. UNATHORIZED DISCLOSURE MAY CONSTITUET TRADE SECRET MASPPROPRISHED AND FREIN AND YED APTENTED OR BE THE SUBJECT OF PENDING PATENT APPLICATION. ANYONE VIOLATING THE INTENT OF THIS SUBJECT OF PENDING PATENT APPLICATION. ANYONE VIOLATING THE INTENT OF THIS SUBJECT OF PENDING PATENT APPLICATION. ANYONE VIOLATING THE INTENT OF THIS SOPYRIGHT PROTECTION WILL BE PROSECUTED TO THE FULL EXTENT OF THE FEDERA STATE AND LOCAL LAWS.





ervices GRUSS IN A Transport Development 115 N. 170 ANN. EECH 600

Johnson County Court Sel

REVISIONS


DESCRIPTION DAT


PROJECT NO. ISSUE DATE
2301301 8-30-2024

SUBMITTAL
100% Construction Document Set

MISCELANEOUS DETAILS

C-901





BACK OF CURB / BED LINE

GROUNDCOVER SPACING DETAIL

NOT TO SCALE


ITE INTERIOR LANDSCAPE TREES PROVIDED =

ROOTBALL

SHRUB/GROUNDCOVER PLANTING DETAIL

ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED BY

NO EARTHWORK DISTURBING ACTIVITY MAY COMMENCE UNTIL A STORM WATER MANAGEMENT PERMIT IS OBTAINED.



SCOPE OF WORK

MIX TO ALL PLANTING BEDS — CROWNING FOR PROPER DRAINAGE. (SE SPECIFICATIONS FOR MORE DETAILED INSTRUCTION ON TURF AREA ANI

PLANTING BED PREPARATION.)

2. A THREE INCH DEPTH OF SHREDDED HARDWOOD BARK MULCH WILL BE USED AS A TOPDRESSING FOR ALL PLANTING BEDS AND TREE RINGS.

3. LANDSCAPE CONTRACTOR SHALL MAKE OWN PLANT QUANTITY TAKEOFFS USING DRAWNOS, SPECIFICATIONS AND PLANT SCHEDULE. PLANT SCHEDULE PLANT SCHEDULE. REQUIREMENTS (I.E. SPACING) DICTATE, UNLESS OTHERWISE DIRECTED BY THE LANDSCAPE DESIGNER. LANDSCAPE CONTRACTOR TO VERIFY BED MEASUREMENTS AND INSTALL APPROPRIATE QUANTITIES AS GOVERNED BY THE THE PLANT SPACING PER THE SCHEDULE. ENSURE ALL MINIMUM REQUIREMENTS OF THE LOCAL GOVERNING AUTHORITY ARE MET (I.E

MINIMUM PLANT QUANTITIES.)
4. NO SUBSTITUTIONS OF PLANT MATERIALS WILL BE ALLOWED. IF PLANTS ARE NOT AVAILABLE, THE LANDSCAPE CONTRACTOR SHALL NOTIFY THE LANDSCAPE DESIGNER IN WRITING (VIA PROPER CHANNELS). PLANTS MAY BE INSPECTED AND APPROVED OR REJECTED ON THE JOBSITE BY THE OWNER OR THE OWNER'S REPRESENTATIVE.

5. LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR THE LANDSCAPE MAINTENANCE OF THIS PROJECT UNTIL FINAL ACCEPTANCE. TURF AREAS WILL NOT BE ACCEPTED UNTIL THEY AREA AT A MINIMUM OF 1-1/2 INCHES TALL, AND NO BARE AREAS LARGER THAN 12 SQUARE INCHES.

LANDSCAPE PLANTING SPECIFICATIONS QUALIFICATIONS OF LANDSCAPE CONTRACTOR

- 1. THE LANDSCAPING SHALL BE PERFORMED BY A SINGLE FIRM SPECIALIZING IN LANDSCAPE PLANTING.

 2. A LIST OF SUCCESSFULLY COMPLETED PROJECTS OF THIS TYPE, SIZE AND NATURE MAY BE REQUESTED BY THE OWNER FOR FURTHER QUALIFICATION MEASURES.
- MEASURES.

 3. THE LANDSCAPE CONTRACTOR MUST HOLD A VALID NURSERY AND FLORAL CERTIFICATE ISSUED BY THE INDIANA DEPARTMENT OF AGRICULTURE, AS WELL AS OPERATE UNDER A COMMERCIAL PESTICIDE APPLICATOR LICENSE—ISSUED BY EITHER THE INDIANA DEPARTMENT OF AGRICULTURE OR THE
- ALL MANUFACTURED PRODUCTS WILL BE NEW. TOPSOIL: A FRIABLE, LOAMY TOPSOIL (OR SILTY SAND) WITH MINIMAL CLAY CLODS.
 3. PLANTING MIX: AN EQUAL PART MIXTURE OF TOPSOIL, SAND AND COMPOST.
 4. STARTER FERTILIZER: A 13-13-13 RATIO WITH 25% SCU, 5% SULFUR, 2% IRON AND ADDITIONAL MICRONUTRIENTS. IRON AND ADDITIONAL MICRONOLINENTS.

 PRE-EMERGENCE: ANY GRANULAR, NON-STAINING PRE-EMERGENCE THAT IS LABELED FOR THE SPECIFIC ORNAMENTALS OR TURF IT WILL BE UTILIZED ON. A PRE-EMERGENCE HERBICIDE IS TO BE APPLIED PER THE
- 6. MULCH: AS SPECIFIED ON THE PLANTING PLAN WELL DECOMPOSED. MOLCH. AS SPECIFIED ON THE LANTING PILAT WELL DECOMPOSED
 TEEL EDGING: PROFESSIONAL STEEL EDGING, 14 GAUGE THICK X 4 INCHES WIDE FACTORY PAINTED DARK GREEN. ACCEPTABLE MANUFACTURERS INCLUDE COL—MET OR APPROVED EQUAL.

 WEED BARRIER: A 5 OUNCE, WOVEN, NEEDLE—PUNCHED FABRIC. ACCEPTABLE PRODUCT INCLUDES DEWITT PRO 5, OR APPROVED EQUAL. 9. TREE STAKES: 6' GREEN METAL T-POSTS

TREE PLANTING

- TREE HOLES SHALL BE EXCAVATED TO A WIDTH OF TWO TIMES THE WIDTH OF THE ROOTBALL, AND TO A DEPTH EQUAL TO THE DEPTH OF THE ROOTBALL (LESS TWO INCHES).

 SCARIFY THE SIDES AND BOTTOM OF THE TREE HOLE PRIOR TO THE PLACEMENT OF THE TREE. REMOVE ANY GLAZING THAT MAY HAVE BEEN CAUSED DURING THE EXCAVATION OF THE HOLE.

 INSTALL THE TREE SO THE TOP OF THE ROOTBALL IS ONE TO TWO INCHES ABOVE THE SURPOLINDING CRADE. ABOVE THE SURROUNDING GRADE.

 4. BACKFILL THE TREE HOLE UTILIZING THE EXISTING TOPSOIL FROM ON—SITE. CLAY, ROCKS AND OTHER DEBRIS SHALL BE REMOVED FROM THE SOIL PRIOR TO THE BACKFILL. SHOULD ADDITIONAL SOIL BE REQUIRED TO ACCOMPLISH THIS TASK, IMPORT ADDITIONAL TOPSOIL FROM OFF—SITE, ADD NO ADDITIONAL COST TO THE OWNER.

 5. THE TOTAL NUMBER OF TREE STAKES (BEYOND THE MINIMUM'S LISTED DELOW) WHILL BE LIEST TO THE LANDSCADE CONTRACTOR'S DISCORPTION. BELOW) WILL BE LEFT TO THE LANDSCAPE CONTRACTOR'S DISCRETION
 SHOULD ANY TREES FALL OR LEAN, IT WILL BE THE RESPONSIBILITY OF THE
 LANDSCAPE CONTRACTOR TO STRAIGHTEN THE TREE, OR REPLACE IT
 SHOULD IT BECOME DAMAGED. TREE STAKING WILL CONSISTS OF, AT A
 MINIMILIE
- MINIMUM:

 15 30 GAL TREES

 45 100 GAL TREES

 (2) STAKES PER TREE

 45 100 GAL TREES

 (3) STAKES PER TREE

 MULTI-TRUNK TREES

 NO MINIMUM

 6. UPON COMPLETION OF THE PLANTING, AN EARTH WATERING BASIN WILL BE
 CONSTRUCTED AROUND THE TREE. THE INTERIOR OF THE TREE RING WILL
 THEN BE COVERED WITH THE WEED BARRIER CLOTH, AND TOPDRESSED WITH
 A THREE INCH LAYER OF MULCH.
- DURING LANDSCAPE PREPARATION AND PLANTING, KEEP ALL PAVEMENT CLEAN AND ALL WORK AREAS IN A NEAT, ORDERLY CONDITION.
 ALL EXCAVATED MATERIALSWILL BE DISPOSED OF LEGALLY OFF THE PROJECT SITE.

INSPECTION AND ACCEPTANCE

1. UPON COMPLETION OF THE WORK, PROVIDE THE SITE CLEAN AND FREE OF 1. UPON COMPLETION OF THE WORK, PROVIDE THE SITE CLEAN AND FREE OF MATERIALS AND SUITABLE FRO USE AS INTENDED.
2. WHEN THE PLANTING WORK IS COMPLETED, THE OWNER WILL MAKE AN INSPECTION TO DETERMINE ACCEPTABILITY.
3. WHEN THE INSPECTED PLANTING WORK DOES NOT COMPLY WITH THE CONTRACT DOCUMENTS, REPLACE THE REJECTED WORK WITHIN 24 HOURS.
4. LANDSCAPE MAINTENANCE WILL CONTINUE UNTIL RE-INSPECTED BY THE OWNER AND FOUND TO BE ACCEPTABLE. ONCE ACCEPTABLE, FINAL ACCEPTANCE WILL BE ISSUED, AND THE REQUIRED MAINTENANCE PERIOD WILL COMMENCE.

EXISTING UTILITY SIZE AND MATERIAL

INFORMATION SHOWN ON THESE PLANS ARE PER

THE BEST GRAPHICAL AND VISIBLE INFORMATION

AVAILABLE. CONFLICTS MAY EXIST AND IT SHALL

BE THE CONTRACTOR'S RESPONSIBILITY TO FIELD

VERIFY ALL SIZING AND MATERIAL INFORMATION

THAT INFORMATION SHOWN ON THE PLANS, THE

CONTRACTOR SHALL, PRIOR TO THE INSTALLATION

OF ANY PROPOSED INFRASTRUCTURE, NOTIFY THE

DESIGN ENGINEER IMMEDIATELY.

PROVIDED. IF ACTUAL CONDITIONS DIFFER FROM

1. WORK COVERED BY THESE SECTIONS INCLUDES THE FURNISHING OF PAYING FOR ALL MATERIALS, LABOR, SERVICES, EQUIPMENT, LICENSE TAXES AND ANY OTHER ITEMS THAT ARE NECESSARY FOR THE EXECUTION INSTALLATION AND COMPLETION OF ALL WORK, SPECIFIED HEREIN AND / C INSTALLATION AND COMPLETION OF ALL WORK, SPECIFIED HEREIN AND / OR SHOWN ON THE LANDSCAPE PLAN.

2. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE LAWS, CODES AND REGULATIONS REQUIRED BY AUTHORITIES HAVING JURISDICTION OVER SUCH WORK AND PROVIDE ALL INSPECTIONS AND PERMITS REQUIRED BY FEDERAL, STATE AND LOCAL AUTHORITIES IN SUPPLY, TRANSPORTATION AND INSTALLATION OF MATERIALS.

3. THE LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR THE VERIFICATION OF ALL INDEPORCEMENT LANDS CAPE OF THE VERIFICATION OF THE

ALL UNDERGROUND UTILITY LINES (TELEPHONE, GAS, WATER, ELECTRICAL CABLE, TELEVISION, ETC...) PRIOR TO THE START OF ANY WORK.

 PROVIDE PLANTS TYPICAL OF THEIR SPECIES OR VARIETY, WITH NORMAL, DENSELY DEVELOPED BRANCHES AND VIGOROUS, FIBROUS ROOT SYSTEMS.
 PROVIDE ONLY SOUND, HEALTHY, VIGOROUS PLANTS FREE FROM DEFECTS, DISFIGURING KNOTS, SUNSCALD INJURIES, FROST CRACKS, ABRASIONS OF THE BARK, PLANT DISEASE, INSECT EGGS, BORERS AND ALL OTHER FORMS THE BARK, PLANT DISEASE, INSECT EGGS, BORERS AND ALL OTHER FORMS OF INFESTATION.

3. ALL PLANTS SHALL BE BALLED AND BURLAPPED OR CONTAINER GROWN AS SPECIFIED. NO CONTAINER GROWN STOCK WILL BE ACCEPTED IF IT IS ROOT BOUND. ALL ROOT WRAPPING MATERIAL MADE OF SYNTHETICS SHALL BE REMOVED AT TIME OF PLANTING.

4. ALL MATERIAL SHALL CONFORM TO THE GUIDELINES ESTABLISHED BY THE AMERICAN ASSOCIATION OF NURSERYMAN.

5. CRACKED OR MUSHROOMED ROOTBALLS ARE NOT ACCEPTABLE.

6. CALIPER MEASUREMENT FOR STANDARD (SINGLE TRUNK) TREES SHALL BE TAKEN AS FOILOWS: SIX INCHES ABOVE THE NATURAL GRADE LINE FOR

TAKEN AS FOLLOWS: SIX INCHES ABOVE THE NATURAL GRADE LINE FOR TREES UP TO AND INCLUDING FOUR INCHES IN CALIPER; AND TWELVE INCHES ABOVE THE NATURAL GRADE LINE FOR TREES EXCEEDING FOUR INCHES IN CALIPER – UNLESS SPECIFIED DIFFERENTLY ON THE LANDSCAPE DIAM. 7. MULTI-TRUNK TREES SHALL BE MEASURED BY THEIR OVERALL PLANTED

SHRUB AND GROUNDCOVER PLANTING

1. UPON APPROVAL OF THE GRADE LEFT BY THE GENERAL CONTRACTOR, THE LANDSCAPE CONTRACTOR WILL ROTOTILL THE PROPOSED BED LOCATIONS (BEFORE ADDING THE IMPORTED SOIL). A FOUR INCH DEPTH OF THE SPECIFIED PLANTING MIX WILL THEN BE EVENLY SPREAD OVER THE DESIGNATED BED AREA. THE PLANTING BED WILL THEN BE ROTOTILLED AGAIN, AND A PRE-EMERENCE AND STARTER FERTILIZER WILL BE APPLIED.

2. THE PLANTING BED WILL THEN BE HAND RAKED SMOOTH AND CROWNED FOR PROPER DRAINGS. 3. DIG THE HOLD TWICE AS WIDE AS THE PLANT'S ROOTBALL. INSTALL T PLANT IN THE HOLE. BACKFILL AROUND THE PLANT.

4. INSTALL THE WEED BARRIER CLOTH, OVERLAPPING IT AT THE ENDS. UTILIZE STELL STAPLES TO KEEP THE WEED BARRIER CLOTH IN PLACE.

5. A TWO INCH DEPTH OF MULCH WILL THEN BE INSTALLED AS A TOP DRESSING, COVERING THE ENTIRE PLANTING AREA.

TURE AREA PREPARATION

1. THE GENERAL CONTRACTOR WILL LEAVE ALL TURF AREAS (EXCLUDING TH DETENTION PONDS) AT TWO (2) INCHES BELOW FINAL GRADE. THE LANDSCAPE CONTRACTOR SHALL IMPORT AND SPREAD A COMPACTED TWO INCH DEPTH OF LOAMY TOPSOIL — ENSURING THE SOIL IS COMPACTED.

2. LANDSCAPE CONTRACTOR WILL ENSURE ALL AREAS ARE CROWNED FOR PROPER DRAINAGE

3. APPLY THE STARTER FERTILIZER.

 SOD VARIETY TO BE AS SPECIFIED ON THE LANDSCAPE PLAN.
 LAY SOD WITHIN 24 HOURS FROM THE TIME OF STRIPPING. DO NOT LAY IF THE GROUND IS FROZEN.
 LAY THE SOD TO FORM A SOLID MASS WITH TIGHTLY FITTED JOINTS. BUTT ENDS AND SIDES OF SOD STRIPS — DO NOT OVERLAP. STAGGER STRIPS TO OFFSET JOINTS IN ADJACENT COURSES.
 WATER THE SOD THOROUGHLY WITH A FINE SPRAY IMMEDIATELY AFTER PLANTING TO OBTAIN AT LEAST SIX INCHES OF PENETRATION INTO THE SOL BELOW THE SOD. BELOW THE SOD.

5. ROLL THE SOD TO ENSURE GOOD CONTACT OF THE SOD'S ROOT SYSTEM

HYDROMULCHING

35# CELLULOSE FIBER MULCH
2# FESCUE SEED
1# ANNUAL RYE SEED
10# 15-15-15 WATER SOLUBLE FERTILIZER

WITH THE SOIL UNDERNEATH.

1. THE MAINTENANCE PERIOD SHALL COMMENCE ONCE FINAL ACCEPTANCE HAS BEEN ISSUED BY THE OWNER, AND SHALL CONTINUE FOR A PERIOD OF NINETY (90) DAYS. 2. THE MONITORING AND SCHEDULING OF THE IRRIGATION SYSTEM WILL BE THE RESPONSIBILITY OF THE LANDSCAPE CONTRACTOR DURING THIS TIME. COORDINATE ALL SCHEDULING AND ANY ACCESS REQUIREMENTS WITH THE J. LANDSCAPE MAINTENANCE SHALL INCLUDE, BUT NOT BE LIMITED TO:
WEEKLY SITE VISITS FOR MOWING, EDGING, BLOWING, WEEDING, TRIMMING,
PRUNING, FERTILIZING, WEED CONTROL, INSECT CONTROL, DISEASE CONTROL,
RE-STAKING, RE-SETTING OF PLANTS TO THEIR PROPER GRADE OR THEIR
UPRIGHT POSITION, AND ANY OTHER MEANS TO KEEP THE PLANTINGS

WARRANTY PERIOD, PLANT GUARANTEE AND REPLACEMENTS

. PLANT MATERIALS SUPPLIED SHALL BE WARRANTIED TO REMAIN ALIVE AN HEALTHY FOR A PERIOD OF TWELVE (12) MONTHS AFTER THE DATE OF FINAL ACCEPTANCE BY OWNER SEASONAL ANNUALS FOR 90 DAYS FROM FINAL ACCEPTANCE . PLANTS IN AN IMPAIRED, DEAD OR DYING CONDITION AFTER INITIAL ACCEPTANCE OR WITHIN THE WARRANTY PERIOD SHALL REMOVED AND REPLACED IMMEDIATELY TO THE SATISFACTION OF THE OWNER.

HEALTHY, FREE OF INSECTS AND DISEASES, AND IN A CONTINUAL THRIVING

1. PROVIDE A MINIMUM OF (2) COPIES OF RECORD DRAWINGS TO THE OWNER UPON COMPLETION OF WORK. A RECORD DRAWING IS A RECORD OF ALL CHANGES THAT OCCURRED IN THE FIELD AND THAT ARE DOCUMENTED THROUGH CHANGE ORDERS, ADDENDA, OR CONTRACTOR/CONSULTAN



ARCHITECTURE 111 E. Wayne Street, Suite 555, Fort Wayne, IN 46802


260 424-9080 ElevatusArchitecture.com

S2 ARCHITECTS, LLC dba ELEVATUS ARCHITECTURE PURSUANT TO SECTION 102 OF THE COPYRIGHT ACT, 17 U.S.C., ALL CONCEPTS, ID DESIGNS, ARRANGEMENTS, DRAWNINGS, AND PLANS INDICATED OR REPRESENTED HIS DOCUMENT ARE COPYRIGHTED BY SEACHTECTS, LIC das ELEVATUS ARCHITECTURE. AS SUCH ALL CONCEPTS, IDEAS, DESIGNS, ARRANGEMENTS, DESIGNS, DRAWNINGS AND ARCHITECTURE.

PURSUANT TO SECTION 102 OF THE COPYRIGHT ACT, 17 U.S.C., PROTECTION FOR AN ARCHITECTURAL WORK CREATED AS A WORK MADE FOR HIRE ON OR AFTER DECEM

STATE AND LOCAL LOWS.

WRITTEN DIMENSIONS ON THESE DOCUMENTS SHALL HAVE PRECEDENCE OVER SCALE
DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSION
AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATION
FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP
DRAWINGS AND OR DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR REVIEW BEFOR
PROCEEDING WITH FABRICATION.





B

County ROAD FRA

O ohns 07

REVISIONS

DESCRIPTION

ISSUE DATE 2301301 8-30-2024 UBMITTAL

100% Construction Document Set ANDSCAPE PLAN

L-1000

TREE/300 SFT. REQUIRED LANDSCAPE AREA

ARKING LOT INTERIOR LANDSCAPE TREES PROVIDED = 35 TREES

= 6 SHRUBS

SHRUB/80 LINEAR FEET

25 TREES